BRUHAT BANGALORE MAHANAGARA PALIKE

BYATARAYANAPURA DIVISION

Name of Work: Resetting of Chainlink Fencing implimentaion of rainwater harvesting and implimentaion to park at Sahakarnagar park in ward No.8

MODIFIED SCHEDULE - B

Item No	Quantity	Description of work	Unit	M/S KRIDL	
				In Figures	In Words
1	34.69	KSRRB M200-13.1. Dismantling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceble material and stacking the serviceble material with all lifts complete as per specifications. II. By mechanical means, A. Cement concrete Grade M-15 & M-20	Cum	522.40	Rupees Five Hundred Twenty Two and Paise Forty Only
2	2.84	KSRRB M200-15.2. Dismantling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceble material and stacking the serviceble material with all lifts complete as per specifications. iii) Dismantling Stone Masonry B. Rubble Stone maonry in cement mortar	Cum	372.06	Rupees Three Hundred Seventy Two and Paise Six Only
3	67.61	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3	Cum	252.49	Rupees Two Hundred Fifty Two and Paise Forty Nine Only
4	41.00	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2.	Cum	5505.64	Rupees Five Thousand Five Hundred Five and Paise Sixty Four Only
5	3.44	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	Cum	4871.76	Rupees Four Thousand Eight Hundred Seventy One and Paise Seventy Six Only
6	46.80	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sq-m	149.46	Rupees One Hundred Forty Nine and Paise Forty Six Only
7	6.40	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.530 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2.	Cum	5747.32	Rupees Five Thousand Seven Hundred Forty Seven and Paise Thirty Two Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Scanned by TapScanner

Item No	Quantity	Description of work	Unit	M/S KRIDL	
				In Figures	In Words
8	12.13	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should bethoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification	Sq-m	3192.72	Rupees Three Thousand One Hundred Ninety Two and Paise Seventy Two Only
9	461.10	KSRRB M800-7. Painting:-Providing and applying two coats of ready-mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications.MORTH Specification No. 803 Painting on Steel Surface	Sq-m	76.32	Rupees Seventy Six and Paise Thirty Two Only
10	423.54	KSRRB M400-19: Construction of Median and island above road level with approved material deposited from borrowpits, spread, sloped and compacted as per Clause 400.7 complete as per specifications. MORTH Specification No.407	Cum	221.54	Rupees Two Hundred Twenty One and Paise Fifty Four Only
11	131.00	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	m	910.54	Rupees Nine Hundred Ten and Paise Fifty Four Only
12	269.70	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint	Sq-m	757.90	Rupees Seven Hundred Fifty Seven and Paise Ninety Only
13	269.70	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.	m	432.48	Rupees Four Hundred Thirty Two and Paise Forty Eight Only
14	369.20	KSRB 14.6-1: Providing & laying heavy duty cobble stones 60mm thick interlock pavers,using cement & course sand for manufacture of blocks of approved size ,shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (Avg thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS	Sq-m	1116.18	Rupees One Thousand One Hundred Sixteen and Paise Eighteen Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Scanned by TapScanner

Item No	Quantity	Description of work	Unit	M/S KRIDL	
				In Figures	In Words
15	560.00	Providing and fixing precast solid concrete kerb stones made out of CC. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete	No	467.46	Rupees Four Hundred Sixty Seven and Paise Forty Six Only
16	509.45	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8	Sq-m	84.80	Rupees Eighty Four and Paise Eighty Only
17	7.50	KSRRB 2.6:Providing and filling Stone Dust in trenches to required depth including watering ramming with all leads and lift. complete as per specification and as directed by Engineer-in-charge	Cum	1432.12	Rupees One Thousand Four Hundred Thirty Two and Paise Twelve Only
18	10.00	Providing and making precast seating arrangement including excavation laying pcc M15, providing laying M20 concrete for pedestal and seating slab, fixing of seating slab including all necessary bolt and nuts etc, complete and as per the directions of Engineer in-Charge. (Data Rate)	Each	11785.00	Rupees Eleven Thousand Seven Hundred Eighty Five Only
E1	1286.40	KSRRB 200-8. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. MORTH / Chapter 2	Sq-m	10.60	Rupees Ten and Paise Sixty Only
E2	38.70	Removing and resetting of footpath slab	Sq-m	208.82	Rupees Two Hundred Eight and Paise Eighty Two Only
E3	4.00	Modern Dust Bins	No	14445.00	Rupees Fourteen Thousand Four Hundred Forty Five Only
E4	1.00	Supply and fixing of children Play Equipment Four Seater Seesaw SPECIFICATIONS The See Saw consists of 2 poles of Dia 114mm and thickness of 2 5mm which balances the 16 horizontal rod at the center which is of size 3110 mm length and Dia 114 mm. It consists of 4 seats which is made of LLDPE virgin plastic of size 305mm X 213 mm X 125 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges	Each	107240.00	Rupees One Lakh Seven Thousand Two Hundred Forty Only

Note:-

1 The work should be executed as per the Specification and standard specified by the PWD and other Specification of BBMPand Directed

2 The Work should be Carried out as per the Directions and instructions of the Concerned Engineer

3 The Contractor should maintain the quality of work as per the standard specification

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Bruhat Bangaluru Mahanagara Palike

Scanned by TapScanner